BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of the Work: Providing Recharging Pits to Existing Borewell Points Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	83.63	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, **in hard soil** not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods etc complete as per specifications and directions of engineer in	Cum	588.38	Rupees Five Hundred Eighty Eight and Thirty Eight Paise Only
2	63.00	Laying Reinforced cement concrete pipe NP4 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications. MORTH Specification No. 2900 B. 1200 mm dia etc complete as per specifications and directions of engineer in charge of the work	m	10753.70	Rupees Ten Thousand Seven Hundred Fifty Three and Seventy Paise Only
3	7.42	Providing and **Filling in foundation with granite / trap broken metal** 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. etc complete as per specifications and directions of engineer in charge of the work	Cum	2574.74	Rupees Two Thousand Five Hundred Seventy Four and Seventy Four Paise Only
4	116.29	0734 - Providing Aggregate 53 mm nominal size etc complete as per specifications and directions of engineer in charge of the work	Cum	1054.29	Rupees One Thousand Fifty Four and Twenty Nine Paise Only
5	7.42	0750 - Providing Aggregate 40 mm nominal size etc complete as per specifications and directions of engineer in charge of the work	Cum	1091.43	Rupees One Thousand Ninety One and Forty Three Paise Only
6	7.42	0749 - Providing Aggregate 20 mm nominal size etc complete as per specifications and directions of engineer in charge of the work	Cum	1091.43	Rupees One Thousand Ninety One and Forty Three Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	4.95	0334 - Providing sand / Artifical Sand / Manufactured sand etc complete as per specifications and directions of engineer in charge of the work	Cum	1591.43	Rupees One Thousand Five Hundred Ninety One and Forty Three Paise Only

"DTS APPROVED"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))